

Conditions for Concrete Work Status as of 02/2020

LÖFKENFELD 65 . 33397 RIETBERG

FON +49 (0) 29 44. 97 02-0 FAX +49 (0) 29 44. 97 02-33

VERWALTUNG@HORSTKEMPER.DE WWW.HORSTKEMPER.DE

The following conditions for concrete work are an extension to our installation conditions 02/2020 and are as such applicable contiguously.

4.2 **Building Site - Prerequisites**

- 4.2.1 During the installation work the following connections in close proximity, max. however 60 m to our tools and equipment is to be provided free of cost: Electricity 380 V /32 A idle), water connection 1/2" approx. 2-4 bar rubble dumpers and waste water containers in adequate size
- 4.2.2 The client shall provide us with a work area of the size of the entire track system accessible on all sides by 2.00 m.
- 4.2.3 The marking of trenches and stipulation of track height will be carried out by our workers. The technical requirements of the foundation work and concrete cutting work will be provided for checking and approval to the client based on our drawings. We do not take any liability for damages, which occur due to the severing of invisible cables/reinforcement.
- Rails will be laid horizontally in the sole (minimum seat depth 75% of the track profile). 4.2.4 If this is not possible due to the site, additional costs might occur for the client. Similarly separate additional costs would be levied for interruptions not caused by us. Necessary lifting devices (forklifts, cranes) should be provided free of cost at the construction side.

Volksbank Rietberg eG